# LA-306 Quick Startup Guide



Figure 1-1 LA-306 Control Console

### **Prepare furnace**

- Verify white Main Power light is ON. Verify EMO switches are closed (including safety switch inside control console enclosure).
- b. Make sure all Energize Lamps switches are properly ON or OFF per process requirements (Fig 1-2).
- Press green CONTROLS ON button (Fig 1-3) to enable the control system. Belt & fans will start. Source process gas solenoid valve will open.

### **Set flowmeters**

- a. Verify process gas source pressure is 65-75 psi.
- b. Verify gas flow at each flowmeter meets profile requirements. Adjust individual flowmeters to suit.

#### **Set temperature**

Verify or adjust zone temperature settings for the profile you are running. To adjust each controller:

- a. Press Up or Down button until green SV displays correct setpoint temperature (Fig 1-4).
- b. Press Set button.

## Verify or adjust belt speed setpoint

- To adjust, press Enter (E) button next to Belt Speed display (Fig 1-5) to adjust the leftmost digit.
- b. Press UP or DOWN arrow until desired value shows.
- c. Press E to lock in first digit and move to the next digit. Pressing E after rightmost digit is set returns speed controller to operating mode.
- d. Let the belt speed settle 2-3 minutes before pressing Lamps ON button.

### Start furnace lamps

- a. Press green Lamps ON button.
- b. Wait 30 minutes after green Status Ready lamp is lit.
- c. Place product on belt.

Note: For best results, after Ready light turns ON allow furnace to run for 30-45 minutes at process temperatures before inserting product. Start each production run with two dummy product carriers. Closely follow with product carriers 1/2" to 3/4"apart on belt.



Figure 1-2 Energize Lamps



Figure 1-3 Controls and Lamps buttons



Figure 1-4 Temperature controller



Figure 1-5 Speed Adjust

### LA-306 Shutdown

- a. Press COOL DOWN button (fig 1-3). Lamps shut off immediately. Controls stay on, belt and fans keep running. Process gas valve stays open.
- Furnace belt and fans will operate until control enclosure reaches below 80°C. Then Process Gas valve closes and fans, belt and controls shut off.

### **LA-306 Flowmeter Notes**

**SEALS.** For furnaces equipped with a SEALS flowmeter, to prevent damage to the element seals and avoid premature lamp failure:

- a. When operating at 400°C or below, set the SEALS flowmeter to at least 12 L/min.
- b. As a guide, when operating above 400°C, increase flow a minimum of 2.5 L/min for each 100°C the furnace is operated above 400°C. For example, for 800°C operation adjust SEALS to 22 L/m.

**COOLING.** To prevent damage to the CACT aluminum heat exchanger:

- a. When operating at 200°C or below, set the COOLING to suit process parts cooling requirements.
- READY

  ALARMS

  ZONE TEMP DEVIATION
  OVER TEMPERATURE
  AIR PRESSURE LOW
  N2 PRESSURE LOW
  FG PRESSURE LOW
  CLEAR

Figure 1-6 Status Ready

b. When operating above 200°C, set COOLING to a minimum of 8 L/m (for 200°C in Zone 3) plus 2.5 L/min per 100°C above 200°C to protect CACT, or higher to suit process parts cooling requirements. For example, at 800°C in Zone 3 set COOLING to 23 L/min.

**NITROGEN FIRING.** When firing in nitrogen, make sure to allow adequate time for furnace to purge oxygen from internals.

- a. If furnace is just being started, allow at least 30 minutes after green Ready lamp is lit.
- b. If furnace has been operating on nitrogen, you can start processing almost immediately after temperatures have settled and green Ready lamp is lit.
- c. If furnace has been operating on CDA, allow at least 30 minutes after switching to nitrogen and green Ready lamp is lit.

Note: To further reduce oxygen concentrations in furnace, increase gas flow to Zone 1 and Zone 2-3 rather than increasing flow to baffles. Also decreasing flow slightly to Stack flowmeter can often lower O<sub>2</sub> concentrations in the chamber zones.

# LA-306 Lamp Check

During startup from a cold start, all enabled red TEST LED's should light. To check lamps:

- a. From a cool start, press green CONTROLS button.
- Turn ON the top and bottom ENERGIZE LAMPS switches (figure 1-2) for the Zone you are testing. Press green LAMPS ON button.
- All LED's for selected lamps should light during initial startup.



Figure 1-7 Standard Zone Lamp Strings

d. Repeat steps b & c. above for each set of lamps to be tested. Any LED's that do not light at all indicate a failure of a lamp string. Consult manual or TEC-251 to further troubleshoot.